



THE ADMINISTRATION OF UNION TERRITORY OF LADAKH
OFFICE OF THE DIRECTOR FIRE AND EMERGENCY SERVICES UT LADAKH
(e-mail: igp-ladakh@police.ladakh.gov.in)

(Office Phone No.01982-260888)

No: - PHQ/Dir/F&ES/UTL/2021-477-78

Dated:- 11/1/2022

Subject: Fire NOC in favour of Govt. High School Lalung, Kargil.

The report has been submitted by Superintendent of Police, Fire and Emergency Services, Ladakh regarding the inspection of the instant school which has been done by I/C Fire and Emergency Services, Kargil. The detailed report is as under:

Location/ Accessibility:

The School is constructed at Lalung, Kargil. It is located at Latitude 34.588743 and Longitude 76.289240. The site is approximately 40 Kms away from Fire and Emergency Services Station, Kargil. It takes approximately 01 hour to reach the site which is approachable for fire appliances.

Detail of building:

The school building have three blocks and the detail of the block are as under:

1st block: It is two storied school building having one stair case. In the ground floor there are library and three class rooms. There are two windows in each class room. The size of the windows is 7x5 feet. Two sides of the windows have provision to open. 1st floor have headmaster office, staff room and two class rooms.

2nd block: It is single storied building having ICT room, computer room, sport room, and two store rooms. There are two windows in each room and the size is 5x4 feet. One side of the window have provision to open.

3rd block: It is single storied building having store room, mid-day meal kitchen and dining hall. There are two windows in each room and the size is 5x4 feet. One side of the window have provision to open.

There are 40 students and 12 staffs in the school.

The following Fire Safety equipment's found installed in School Building:

01. 04 no's of fire extinguishers ABC Type 6kg capacity installed in the school building.
02. 02 no's of sand buckets appropriately placed in the school building.
03. 02 no's of plastic water tanks 1000 litres capacity found appropriately placed at the overhead of the School building.

There is a mandatory requirement for keeping 2 exit stair cases in first block of the school building each having at least 1.5 meter width besides constructing 20 thousand litres of underground water tank in school premises along with placing 4 fire extinguishers 6 kg capacity ABC type and 4 sand buckets in the school.

A provisional FIRE NOC for a period of 6 months is given to **Govt. High School Lalung, Kargil** from the date of issuance of this letter and the school management is advised to fulfilling the above listed fire safety requirements in shortest possible time.


Director, F&ES, Ladakh
PHQ, Agaling, Leh

Copy to:

1. Headmaster, Govt. High School Lalung, Kargil for info
2. Superintendent of Police, F&ES, Ladakh for information and n/a